



TYPICAL: BASIS OF DESIGN
 MBCI 5 V CRIMP METAL ROOFING
 INSTALL PER MANUFACTURE AND
 N.O.A.= FL11903 R1

ON GAF 'STORMGUARD' UNDER LAYMENT
 INSTALL PER MANUFACTURE AND
 N.O.A.= 13-1104.11

ON 5/8" CDX PLYWOOD NAILED PER STRUCTURAL DRAWINGS

ON WOOD TRUSSES 24" O.C.- REFER TO STRUCTURALS

UPPER ROOF
 PLAN
 18' - 0"

HARDI-PLANK ON
 30# FELT ON
 5/8" CDX PLYWOOD

2
 SH-1.3

2X6 WOOD STUDS @ 24" O.C.

TYPICAL: BASIS OF DESIGN
 MBCI 5 V CRIMP METAL ROOFING
 INSTALL PER MANUFACTURE AND
 N.O.A.= FL11903 R1

ON GAF 'STORMGUARD' UNDER LAYMENT
 INSTALL PER MANUFACTURE AND
 N.O.A.= 13-1104.11

ON 5/8" CDX PLYWOOD NAILED PER STRUCTURAL DRAWINGS

ON WOOD TRUSSES 24" O.C.- REFER TO STRUCTURALS

CAP BEAM
 10' - 0"

1
 A-5.1

Level 1
 0"

SECTION 3
 3/4" = 1'-0"

Eugene R Fagan III Architect #11668
 3432 A West 45th Street
 West Palm Beach, FL 33418
 (561) 385-4514
 Eugene@FaganArchitect.com

Copyrite 2015	
3/12/2016 1:06:20 PM	

Consultant:
 ANDREW MORGAN SERVICES - STRUCTURAL ENGINEER
 513 US HIGHWAY 1
 SUITE 109
 NORTH PALM BEACH, FLORIDA 33408
 561-881-8999
 AMORGANSERVICES@GMAIL.COM

Consultant
 BD BACH DESIGN ENGINEERS - MECHANICAL ENGINEERS
 381 S.E. 10TH STREET
 POMPANO BEACH, FLORIDA 33060
 954-461-4314
 BACH@BACHENGINEERS.COM

Seal

No.	Description	Date

Sea Ya Holdings
Mary Circle
WALL SECTIONS

Project number	Project Number
Date	Issue Date
Drawn by	Author
Checked by	Checker
A-6.2	
Scale	3/4" = 1'-0"