CONTRACTOR GENERAL CONDITIONS NOTES

- . RFI'S: CONTRACTOR SHALL SUBMIT RFI'S WITH HIS PROPOSED SOLUTION IN A TIMELY MANNER. CONTRACTOR RECOGNIZES THE CONSULTANT SHALL REQUIRE UP TO 5 WORKING DAYS TO RESPOND.
- 2. SUBMITTALS AND PRODUCT DATA: CONTRACTOR SHALL PREPARE A SUBMITTAL SCHEDULE FOR APPROVAL BY THE A/E. CONTRACTOR RECOGNIZES THE CONSULTANT SHALL REQUIRE UP TO 10 WORKING DAYS TO REVIEW SUBMISSIONS. ALL SUBMITTALS, PRODUCT DATA, SHALL BE CLEARLY STAMPED AND INDICATED APPROVED BY THE CONTRACTOR PRIOR TO SUBMISSION TO THE CONSULTANT.
- 3. SHOP DRAWINGS: CONTRACTOR SHALL PREPARE A SHOP DRAWING SCHEDULE FOR APPROVAL BY THE A/E. CONTRACTOR RECOGNIZES THE CONSULTANT SHALL REQUIRE UP TO 10 WORKING DAYS TO REVIEW SHOP DRAWINGS. ALL SHOP DRAWINGS, SHALL BE CLEARLY STAMPED AND INDICATED APPROVED BY THE CONTRACTOR PRIOR TO SUBMISSION TO THE CONSULTANT
- 4. LAYOUT AND COORDINATION DRAWINGS: CONTRACTOR SHALL PREPARE SCALED COMPREHENSIVE COORDINATED LAYOUT DRAWINGS. PROVIDE SECTIONS, GENERAL ARRANGEMENTS, ELEVATIONS INCLUDING ALL DISCIPLINES FOR HIS PROPOSED LAYOUT AND ROUTING PRIOR TO FABRICATION. SUBMIT TO OWNER AND A/E FOR REVIEW AND GENERAL CONFORMANCE. PROVIDE DRAWINGS THAT DEMONSTRATE VIA COORDINATED ELEMENTS AND SYSTEMS WITH STRUCTURE THAT CLEARLY INDICATE PROPOSED SYSTEMS WILL FIT, FUNCTION AS INTENDED, BE FREE OF INTERFERENCES AND CONFORM TO REQUIRED CODE AND MANUFACTURER WORKING AND MAINTENANCE CLEARANCES.
- 5. DEVIATIONS FROM BASIS FOR DESIGN SYSTEMS SHALL BE CLEARLY IDENTIFIED ON ALL SUBMISSIONS. 6. SUBSTITUTIONS:
- A. CONTRACTOR SHALL PREPARE REQUESTS WITH COMPLETE COORDINATION INFORMATION, INCLUDE ALL CHANGES REQUIRED IN OTHER ELEMENTS OF THE WORK TO ACCOMMODATE THE SUBSTITUTION INCLUDING WORK PERFORMED BY THE OWNER AND THE SEPARATE CONTRACTORS.
- B. PROVIDE COMPLETE SUPPORTING DATA QUALIFYING THE SUBSTITUTION COMPARED TO THE BASIS OF DESIGN SYSTEM. PROVIDE A DETAILED LIST OF ANY VARIANCES, PHYSICAL OR SPATIAL LAYOUTS, ELEVATIONS, ETC. TO THE BASIS OF DESIGN.
- C. PROVIDE A STATEMENT INDICATING THE EFFECT THE SUBSTITUTION WILL HAVE ON THE WORK SCHEDULE IN COMPARISON TO THE SCHEDULE WITHOUT APPROVAL OF THE PROPOSED SUBSTITUTION, INCLUDE INFORMATION REGARDING THE EFFECT OF THE PROPOSED SUBSTITUTION ON THE CONTRACT
- D. PROVIDE CERTIFICATION BY THE CONTRACTOR TO THE EFFECT THAT, IN THE CONTRACTOR'S OPINION, AFTER THOROUGH EVALUATION, THE PROPOSED SUBSTITUTION WILL RESULT IN WORK THAT IN EVERY SIGNIFICANT RESPECT IS EQUAL TO OR BETTER THAN THE WORK REQUIRED BY THE CONTRACTOR DOCUMENTS AND THAT IT WILL PERFORM ADEQUATELY IN THE APPLICATION INDICATED.
- E. CONSULTANT'S EXPENSES THAT ARE INCURRED DUE TO REVISIONS OR SUBSTITUTIONS REQUESTED BY THE CONTRACTOR OR APPROVED BY THE OWNER SHALL BE COMPENSATED TO THE CONSULTANT BY
- . AS-BUILT DRAWINGS: THE CONTRACTOR SHALL MAINTAIN AND PREPARE A COMPLETE AND ACCURATE SET OF AS-BUILTS DURING THE PROJECT AND ISSUE TO THE A/E AND OWNER AT PROJECT CLOSEOUT. DURING THE COURSE OF THE PROJECT, THE CONTRACTOR SHALL ISSUE SKETCHES OR SCALED DRAWINGS FOR FIELD CHANGES THAT ARE PROPOSED OR MADE WHICH VARY FROM THE BASIS OF DESIGN. CONSULTANT EXPENSES THAT ARE INCURRED DUE TO SERVICES OR REVISIONS REQUIRED BY BUILDING DEPARTMENT, OWNER, CONTRACTOR, AND MANUFACTURER SHALL BE COMPENSABLE TO THE CONSULTANT BY THE
- 8. INSTALLATION, TESTING AND BALANCING, START UP, COMMISSIONING AND PERFORMANCE TROUBLESHOOTING OF SYSTEMS- CONTRACTOR RECOGNIZES HE IS SOLELY RESPONSIBLE FOR PERFORMANCE AND COMPLETION OF THESE SERVICES AS PART OF THE PROJECT REQUIREMENTS. DURING THE COURSE OF THE PROJECT, THE CONTRACTOR SHALL DOCUMENT THE SERVICES COMPLETED TO THE OWNER AND A/E. CONSULTANT EXPENSES THAT ARE INCURRED DUE TO SUPPORTING SERVICES OR REVISIONS REQUIRED BY BUILDING DEPARTMENT, OWNER, CONTRACTOR, AND MANUFACTURER SHALL BE COMPENSABLE TO THE CONSULTANT BY THE CONTRACTOR.

ф	110V RECEPTACLE	ЦШ	FUSE DISCONNECT
#	QUAD-PLEX RECEPTACLE		ELECTRICAL CIRCUIT BREAKER
₩P	WATER PROOF WITH WR TYPE RECEPTACLE	\boxtimes	FACTORY INSTALLED DISCONNECT
∯ GFI	GROUND FAULT CIRCUIT INTERRUPTER		ELECTRICAL PANEL
 	RECEPTACLE MOUNTED ABOVE COUNTER VERIFY MOUNTING HEIGHT WITH OWNER/ARCHITECT PRIOR TO ROUGH IN		ELECTRICAL METER
	SPECIAL PURPOSE OUTLET (VERIFY)		LIGHTING CONTROL TIME CLOCK/PANEL
Ф	FLOOR RECEPTACLE WITH COVER PLATE, FLUSH WITH FLOOR		TELEPHONE BOARD
(CEILING RECEPTACLE	\$	SWITCH
TATAN	FLOOR RECEPTACLE/TELE/FAX/DATA	\$3	3-WAY SWITCH
	WITH COVER PLATE, FLUSH WITH FLOOR	\$4	4-WAY SWITCH
	FLOOR TELE/FAX/DATA PORT WITH COVER PLATE, FLUSH WITH FLOOR	\$ D	DIMMER SWITCH
lack	TELE/FAX/DATA PORT **	\$m	MANUAL MOTOR STARTER
\bigcirc	CEILING TELE/FAX/DATA PORT **	•	PUSH BUTTON
TV	TELEVISION JACK **	CR	SENSOR DOOR OPENER/CARD READER ** BY OTHERS
<u> </u>	JUNCTION BOX	Α	ALARM BY OTHERS **
	POWER POLE	IG	ISOLATED GROUND
JP	RECESSED JUNCTION BOX FOR SYSTEM FURNITURE POWER	ASW	ABOVE SHOW WINDOW
IJ ^{T/D}	RECESSED JUNCTION BOX FOR	CM	CEILING MOUNTED
2	SYSTEM FURNITURE TELEPHONE/DATA	AC	ABOVE COUNTER
(EF)	EXHAUST FAN	UC	UNDER COUNTER

ELECTRICAL SYMBOL LEGEND

* NOTE: ALL SYMBOLS MAY NOT BE USED FOR THIS PROJECT * * PROVIDE 1"C WITH PULL WIRE UNLESS OTHERWISE NOTED. STUB UP 6" ABOVE CEILING.

THERMOSTAT

(2)_{DD} SMOKE DUCT DETECTOR

CCP CENTRAL CONTROL PANEL

REMOTE ALARM TEST STATION

STEP DOWN TRANSFORMER

OF THE PRODUCT DATA SUBMISSION AND INSTALLATION.

FBC FOR LIGHTING AND HVAC SYSTEMS.

SECTIONS, AND STANDARDS.

RESPONSIBILITIES.

AFF

NO SYMBOL **NEW**

ABOVE FINISHED FLOOR

TELEPHONE GROUND BAR

EXISTING - COORDINATE REPLACING

COVER PLATES W/ OWNER/ARCH

RELOCATED EXISTING - COORDINATI

REPLACING COVER PLATES W/

VERIFY IN FIELD

OWNER/ARCH

RECEPTACLES ARE TO BE MOUNTED AT 18" ABOVE FINISHED FLOOR, UNLESS OTHERWISE NOTED. SWITCHES ARE TO BE MOUNTED AT 48" ABOVE FINISHED FLOOR, UNLESS OTHERWISE NOTED.

SPECIAL PURPOSE OUTLET NOTES

. CONTRACTOR IS CAUTIONED TO OBTAIN COMPLETE EQUIPMENT PRODUCT DATA FROM ARCHITECT, PRIOR TO BIDDING AND ROUGH-IN. 2. CONTRACTOR SHALL PROVIDE NEMA OUTLET TO MEET PROJECT AND EQUIPMENT REQUIREMENTS. CONTRACTOR TO PROVIDE MATCHING NEMA CAP/CORD AS REQUIRED.

UL LISTING AND NRTL CERTIFICATIONS NOTE

CONTRACTOR/MANUFACTURER SHALL PROVIDE COMPLETE DOCUMENTATION AND CERTIFICATIONS FOR ANY EQUIPMENT THAT HE PROPOSES WITH A NRTL (NATIONALLY RECOGNIZED TESTING LAB) LISTING AND LABELING EQUIVALENT TO THE BASIS OF DESIGN UL LISTING. IT IS THE CONTRACTOR'S RESPONSIBILITY TO CONFIRM ACCEPTABILITY BY THE LOCAL AHJ AND AGENCIES FOR THE NRTL LISTING AND CERTIFICATION FOR THE PRODUCTS HE PROPOSES AND DEMONSTRATE SUCH AS PART

FLORIDA BUILDING CODE 2014 CONFORMANCE

CONTRACTOR TO PROVIDE ALL LABOR AND MATERIAL TO CONFORM TO FBC 2014 ENERGY COMPLIANCE, RELATED

OWNER SHALL PROVIDE SERVICES OF AN INDEPENDENT COMMISSIONING AGENT(CxA) TO PREPARE FUNCTIONAL

TEST PROCEDURES (DOCUMENT SYSTEMS PERFORMANCE, WITNESS CONTRACTOR TESTING), AS REQUIRED BY

CONTRACTOR TO PROVIDE COMPLETE CERTIFICATIONS AND CHECKLISTS AS REQUIRED BY FBC FOR HIS WORK

CONTRACTOR SHALL PROVIDE SERVICES TO TEST, BALANCE AND COMMISSION THE SYSTEM VIA AN

INDEPENDENT AGENT FOR THE MECHANICAL SYSTEMS ENERGY PERFORMANCE.

GENERAL ELECTRICAL NOTES

- DO NOT SCALE THE ELECTRICAL DRAWING. REFER TO THE ARCHITECTURAL PLAN AND ELEVATIONS FOR EXACT LOCATION OF ALL EQUIPMENT AND CONFIRM WITH OWNERS REPRESENTATIVES. CONTRACTOR SHALL REFER TO THE ENTIRE SET OF CONTRACT DOCUMENTS FOR PROJECT COORDINATION.
- ALL WORK SHALL BE DONE IN ACCORDANCE WITH THE EDITIONS CURRENTLY ADOPTED BY THE LOCAL AUTHORITIES HAVING JURISDICTION OF THE FOLLOWING: THE NATIONAL ELECTRICAL CODE (NFPA 70), NFPA 72, NFPA 75, THE FIRE PREVENTION CODE INCLUDING NFPA 1 & NFPA 101, NFPA 110, AND THE FBC,
- UNLESS OTHERWISE NOTED. ALL CONDUCTORS SHALL BE COPPER. WITH "THHN" INSULATION FOR SIZE #10 AND SMALLER. CONDUCTORS LARGER THAN #10 SHALL HAVE "THWN" INSULATION. ALL CONDUCTORS IN WET LOCATIONS MUST HAVE "THWN" INSULATION. ALL CONDUCTORS #10 AND SMALLER MAY BE SOLID. ALL CONDUCTORS #8 AND LARGER SHALL BE STRANDED. ALL CONDUCTORS
- OUTLET BOXES SHALL BE PRESSED STEEL IN DRY LOCATIONS, CAST ALLOY WITH THREADED HUBS IN WET LOCATIONS AND SPECIAL ENCLOSURES FOR OTHER CLASSIFIED AREAS.
- DISCONNECT SWITCHES SHALL BE H.P. RATED, HEAVY DUTY, QUICK MAKE, QUICK BREAK, WITH ENCLOSURES AS REQUIRED BY EXPOSURE.
- THESE PLANS DO NOT SHOW EVERY MINOR DETAIL OF CONSTRUCTION, THE CONTRACTOR IS EXPECTED TO FURNISH AND INSTALL ALL ITEMS FOR A COMPLETE ELECTRICAL SYSTEM AND MEET ALL REQUIREMENTS NECESSARY FOR EQUIPMENT TO BE PLACED IN PROPER WORKING ORDER.
- THE ELECTRICAL SYSTEM SHALL BE COMPLETELY AND EFFECTIVELY GROUNDED AS REQUIRED IN ARTICLE 250 NATIONAL ELECTRICAL CODE. THE GROUNDING SYSTEM SHALL BE TESTED AND SHALL BE PROVIDED TO MEASURE A MAXIMUM OF 5 OHMS. PROVIDE A COPY OF THE TEST REPORT TO ENGINEER.
- ALL MATERIALS SHALL BE NEW AND SHALL BEAR U.L. LABELS WHERE APPLICABLE.
- ALL WORK SHALL BE PERFORMED BY A LICENSED ELECTRICAL CONTRACTOR IN A FIRST CLASS WORKMANSHIP MANNER. THE COMPLETE SYSTEM SHALL BE FULLY OPERATIVE AND ACCEPTANCE BY ENGINEER/ARCHITECT MUST BE A CONDITION OF THE SUBCONTRACTOR.
- THE ELECTRICAL INSTALLATION SHALL MEET ALL STANDARD REQUIREMENTS OF POWER, LIGHT COMPANY, TELEPHONE COMPANY, AND BROADBAND PROVIDER.
- CIRCUITS SHOWN ON PLANS ARE TO DETERMINE LOAD DATA AND PANEL SIZE. THE CONTRACTOR SHALL PROVIDE CIRCUITS TO SUIT JOB CONDITIONS, BALANCE LOADS ON EACH PHASE.
- SEE NOTES ON PLANS FOR OTHER REQUIREMENTS.

MUST COMPLY WITH ARTICLE 310 OF THE N.E.C.

- FURNISH AND INSTALL LIGHTING FIXTURES AND LAMPS AS CALLED FOR ON PLANS, OR AS SELECTED BY
- ALL WORK SHALL BE COORDINATED WITH OTHER TRADES TO AVOID INTERFERENCE WITH THE PROCESS
- CORRECTION OF ANY DEFECTS SHALL BE COMPLETED WITHOUT ADDITIONAL CHARGE AND SHALL INCLUDE REPLACEMENT OR REPAIR OF ANY PHASE OF THE INSTALLATION WHICH MAY BE DAMAGED.
- ALL REQUIRED INSURANCE SHALL BE PROVIDED FOR PROTECTION AGAINST PUBLIC LIABILITY OF PROPERTY DAMAGE FOR THE DURATION OF THE WORK.
- CHECK ALL EQUIPMENT FOR PROPER VOLTAGE, PHASE, AND CURRENT BEFORE CONNECTION TO CIRCUITS
- ELECTRICAL CONTRACTOR SHALL CHECK AND VERIFY EQUIPMENT FURNISHED AGAINST THOSE SPECIFIED OR INTENDED AND REVISE BRANCH CIRCUITS AS MAY BE REQUIRED WITH PRIOR APPROVAL OF
- ALL SYSTEMS AND ROUGH-IN SHALL BE CONCEALED IN FINISHED AREAS. COORDINATE WITH ARCHITECT.
- THE ELECTRICAL PORTION OF THE CONTRACT DOCUMENTS ARE COORDINATED WITH THE BASIS OF DESIGN EQUIPMENT SPECIFIED BY DIVISION 16 AND OTHER DIVISIONS. WHERE THE CONTRACTOR ELECTS TO SUBSTITUTE A PRODUCT IN LIEU OF PROVIDING THE DESIGN BASIS, AND SAID SUBSTITUTION IS ACCEPTED BY THE A/E AND OWNER, THE CONTRACTOR SHALL MAKE ALL CORRECTIONS TO THE ELECTRICAL SYSTEM NECESSARY IN ORDER TO ENSURE A COMPLETE AND OPERATIONAL INSTALLATION OF THE EQUIPMENT AT NO ADDITIONAL COSTS. WHERE THE CONTRACTOR'S DECISION TO SUBSTITUTE PRODUCTS OR MODIFY DESIGN REQUIRING A/E SERVICES, THE A/E RESERVES THE RIGHT TO REQUEST COMPENSATION FROM THE CONTRACTOR FOR SAID SERVICES.
- 21. CONTRACTOR SHALL PROVIDE A CONTROLS TRADE SUBCONTRACTOR TO DESIGN AND INSTALL ALL CONTROLS TO MEET THE PROJECT REQUIREMENTS.

AIR CONDITIONING EQUIPMENT AND CONTROLS SPECIFICATION

CONNECTED UNDER THIS SECTION OF THE SPECIFICATION.

- ELECTRICAL CONTRACTOR SHALL INSTALL ALL CONTROL RACEWAY (CONDUIT), WIRE INSTALLATION. CONNECTIONS ETC. IN ACCORDANCE WITH WIRING DIAGRAMS ON AIR EQUIPMENT. A/C / ELECTRICAL PLANS OR DIAGRAMS FURNISHED BY MANUFACTURER OF THE EQUIPMENT. ALL POWER WIRING FOR THE AIR CONDITIONING EQUIPMENT SHALL BE FURNISHED, INSTALLED AND
- MECHANICAL CONTRACTOR SHALL PROVIDE MOTOR STARTERS FOR ALL AIR CONDITIONING EQUIPMENT. ELECTRICAL CONTRACTOR SHALL PROVIDE ALL CONNECTIONS TO AIR CONDITIONING EQUIPMENT PER
- MANUFACTURERS SPECIFICATIONS AIR CONDITIONING EQUIPMENT INCLUDES CONDENSER, COMPRESSOR AND FAN, FAN COIL UNITS, ELECTRICAL STRIP HEATER, THERMOSTAT, ETC.

GENERAL DEMOLITION NOTES

- CONTRACTOR TO EXERCISE EXTREME CAUTION WHEN RELOCATING WIRING DEVICES, EQUIPMENT AND LIGHTING FIXTURES. IT IS THE CONTRACTOR'S RESPONSIBILITY TO INSURE THAT OTHER WIRING DEVICES, EQUIPMENT, AND LIGHTING FIXTURES THAT MAY BE CONNECTED ON THE SAME CIRCUIT REMAIN
- INFORMATION SHOWN ON THESE DOCUMENTS ARE DIAGRAMMATIC IN NATURE. CONTRACTOR TO FIELD
- UPDATE ALL ELECTRICAL PANEL BOARD DIRECTORIES THAT ARE AFFECTED BY THE DEMOLITION AND/OR
- STORE ITEMS INDICATED TO BE RETURNED TO THE OWNER IN A DRY, CLEAN, AND PROTECTED AREA.
- COORDINATE ANY ALTERATION AND CHANGES TO THE ELECTRICAL SERVICE WITH THE LOCAL UTILITY
- PRE SCHEDULE ALL POWER INTERRUPTIONS WITH OWNER. GIVE OWNER 48 HOURS NOTICE PRIOR TO
- POWER TO ALL CRITICAL EQUIPMENT AS NEEDED AND REQUESTED BY OWNER.
- DUE TO REMOVAL OR CORRECTION TO ANY WALLS OR OTHER CONSTRUCTION NECESSITATING CAPPING OF EXISTING ELECTRICAL WIRING DEVICES OR ANY OTHER ELECTRICAL EQUIPMENT INCLUDING RECONNECT OF SUCH EXISTING ITEMS IS CONSIDERED TO BE PART OF THE WORK UNDER THIS CONTRACT. ALL EXISTING OUTLETS SHOWN TO REMAIN WILL REMAIN ACTIVE. THE REWIRING SHALL BE INCLUDED UNDER
- 10. ALL WORK SHALL COMPLY WITH THE LATEST EDITION OF THE FOLLOWING CODES: NATIONAL ELECTRICAL CODE (NEC) NATIONAL FIRE PROTECTION AGENCY (NFPA)

FLORIDA BUILDING CODE

- AREA BY NATURE OF THE ORIGINAL INSTALLATION, CONTRACTOR SHALL MODIFY EXISTING WIRING AS REQUIRED TO MAINTAIN CONTINUITY OF EXISTING CIRCUITRY SUCH THAT NO EQUIPMENT TO REMAIN IS LEFT WITHOUT SERVICE.
- THE CONTRACTOR IS TO GIVE THE OWNER AN OPPORTUNITY TO ACCEPT ANY ELECTRICAL ITEMS THAT TO KEEP SHALL BECOME THE PROPERTY OF THE CONTRACTOR, AND SHALL BE DISPOSED OF BY THE CONTRACTOR, WITHOUT ADDITIONAL COST TO THE OWNER.
- B. CONTRACTOR SHALL PROVIDE TEMPORARY POWER AND LIGHTING WHERE REQUIRED DURING DEMOLITION AND CONSTRUCTION SCOPE OF WORK.
- 4. THE EXISTING CONDITIONS SHOWN ON THESE DRAWINGS ARE TAKEN FROM ORIGINAL DRAWINGS PROVIDED BY THE OWNER AND FIELD INVESTIGATION. THE ACTUAL CONDITIONS MAY VARY, ALL EXISTING CONDITIONS MUST BE VERIFIED PRIOR TO BID. THE CONDITIONS SHOWN ARE INTENDED TO SHOW THE LOCATIONS OF THE EXISTING EQUIPMENT, AND IN NO WAY RELIEVES THE CONTRACTOR FROM PROVIDING ANY AND ALL COORDINATION REQUIRED TO COMPLETE THE NEW WORK. FIELD CONDITIONS
- . THE DEMOLITION PLAN IS NOT INCLUSIVE OF ALL ELECTRICAL DEVICES WITHIN THE PROJECT AREA. IT IS INTENDED TO PROVIDE THE CONTRACTOR WITH A GENERAL KNOWLEDGE OF THE EXISTING CONDITIONS WITHIN THE PROJECT AREA. ANY DISCREPANCIES OR CONDITIONS NOT SHOWN ON THIS PLAN SHALL BE BROUGHT TO THE ATTENTION OF THE ENGINEER. THE CONTRACTOR IS RESPONSIBLE FOR ALL REQUIRED
- ALL CONDUITS SERVING OTHER SPACES OR FLOORS, THAT RUN THROUGH THE PROJECT AREA SHALL REMAIN ACTIVE DURING CONSTRUCTION SO AS NOT TO CAUSE ANY DISRUPTION TO THESE OTHER SPACES. IT IS THE CONTRACTOR'S RESPONSIBILITY TO INSURE THAT ALL CONDUITS, NEW OR EXISTING WITHIN THE PROJECT AREA ARE PROPERLY SUPPORTED AND PROVIDED WITH BONDING BUSHINGS IN
- 17. THE CONTRACTOR SHALL PHASE DEMOLITION WORK AS REQUIRED OR DIRECTED BY THE OWNER.

VOLTAGE DROP NOTE

THE CONTRACTOR, AS PART OF HIS PRICING AND BIDDING, SHALL INCLUDE ALL LABOR, MATERIAL, EQUIPMENT AND TERMINATIONS, INCLUDING FPL AND UTILITY REQUIREMENTS AND APPROVALS FOR ALL CONDUCTORING AND TERMINATIONS, TO SATISFY THE PROJECT REQUIREMENTS. IT IS SOLELY THE CONTRACTOR'S RESPONSIBILITY TO VERIFY AND INCLUDE ALL HIS BRANCH CIRCUIT, FEEDER, AND SERVICE CONDUCTOR CONDUITING AND WIRING LENGTHS AND ROUTING BASED ON HIS PROPOSED INSTALLATION MEANS AND METHODS. WIRING LENGTHS, SHOWN AS THE BASIS OF DESIGN LENGTHS, ARE MERELY AN APPROXIMATION BY THE CONSULTANT. THE CONTRACTOR SHALL USE THOSE BASIS OF DESIGN CONDUCTOR LENGTHS AND WIRING SIZES AS THE, MINIMUM, NOT LIMITED TO REQUIREMENTS FOR THE PROJECT BIDDING. THE CONTRACTOR, PRIOR TO BIDDING, SHALL CONFIRM ALL HIS PROPOSED LENGTHS, MAKE ANY AND ALL ADJUSTMENTS AS MAY IMPACT THE ELECTRICAL SYSTEMS AND EQUIPMENT FOR CODE COMPLIANCE AND CONSTRUCTABILITY, AND DOCUMENT ALL PROPOSED CHANGES AND ADJUSTMENTS TO THE ARCHITECT AS PART OF HIS BID RESPONSE. THE CONTRACTOR SHALL SUBMIT COMPLETE SCALED PROPOSED ROUTINGS FOR SERVICES AND FEEDERS, QUANTITIES AND CONDUCTORING, SECTIONS THRU BUILDING FOR RACKING, DUCTBANK CROSS SECTIONS FOR CLEARANCES AND COORDINATED AS FREE OF ALL INTERFERENCES, ETC. CONTRACTOR SHALL SUBMIT ALL DOCUMENTATION TO THE ARCHITECT FOR REVIEW NO LATER THAN 3 WEEKS AFTER NOTICE TO PROCEED.

- VERIFY ELECTRICAL CIRCUIT HOME RUNS TO ALL ELECTRICAL ITEMS SCHEDULED FOR DEMOLITION AND PERFORM THE WORK AS INTENDED AND DEPICTED ON THE DRAWINGS.
- RENOVATIONS. DIRECTORIES SHALL BE TYPED.
- NOTIFY OWNER WHEN ITEMS ARE READY TO BE REMOVED.
- DISCONNECTING POWER TO ANY PORTION OF THE BUILDING AND MAKE ARRANGEMENTS TO MAINTAIN
- CONTRACTOR IS RESPONSIBLE OF BECOMING FULLY INFORMED AS TO EXISTING CONDITIONS AT THE SITE
- NEITHER THE OWNER NOR THE A/E MAKES ANY REPRESENTATION WARRANTY AS TO SITE CONDITIONS. CONTRACTOR SHALL VISIT THE SITE AND BECOME FAMILIAR WITH THE NATURE AND EXTENT OF THE WORK TO BE PERFORMED AND LOCAL CONDITIONS THAT MAY AFFECT THE WORK.
- THIS CONTRACT WITHOUT ADDITIONAL COST TO OWNER.
- WHERE CONDUIT IS INACCESSIBLE, REMOVE CONDUCTORS AND CUT BACK CONDUIT FLUSH WITH SLAB OR WALL. PATCH OPENING TO MATCH EXISTING FINISH. WHERE EXISTING WIRING EXTENDS OUTSIDE OF THE
- WERE REMOVED FOR THEIR USE. SALVAGED MATERIALS, AND EQUIPMENT THE OWNER DOES NOT WISH
- DEMOLITION WHETHER SHOWN ON THE PLANS OR NOT.
- ACCORDANCE WITH THE NATIONAL ELECTRICAL CODE.
- 18. THE CONTRACTOR SHALL BE RESPONSIBLE FOR REPAIRING OR PATCHING ANY DAMAGE WHICH MAY OCCUR DURING DEMOLITION ACTIVITIES. REPAIRS TO BE DONE TO LOGICAL EDGES OF SURFACES AFFECTED, AND SHALL MATCH IMMEDIATE ADJACENT AREAS IN CONSTRUCTION, MATERIAL, FIRE RATING, FINISH AND COLOR.
- 19. ALL WORK SHALL BE PERFORMED BY A LICENSED ELECTRICAL CONTRACTOR AND SHALL BE COORDINATED WITH OTHER TRADES.

CONTRACTOR TO COORDINATE VARIOUS TRADES TO AVOID ABOVE CEILING CONFLICTS.

ELECTRICAL CONTRACTOR TO VERIFY IF ANY LIGHTING FIXTURES REQUIRE STEP-DOWN TRANSFORMERS. QUANTITY AND LOCATION OF THE TRANSFORMERS TO BE FIELD VERIFIED PRIOR TO CONSTRUCTION. CONSULT ARCHITECT FOR LOCATIONS PRIOR TO BIDDING, PROVIDE ALL TRANSFORMERS AND INCLUDE IN BID.

2. ALL LIGHTING FIXTURES AND FANS TO BE SELECTED & LOCATED BY OWNER /ARCHITECT/INTERIOR DESIGNER. UNLESS OTHERWISE NOTED.

ELECTRICAL SHEET INDEX

FBC NOTE

I. CONTRACTOR SHALL COMPLY WITH FBC (C408.2.5.1). PROVIDE OWNER WITH A RECORD SET DRAWING OF COMPLETE

LOW VOLTAGE NOTES

PROVIDE A STRUCTURED CABLING SYSTEM (SCS) FOR THE TV/CABLE/TELEPHONE DROPS, COORDINATE DESIGN, TYPE

FIRE RATING NOTE

ALL DEVICES PENETRATING FIRE RATED WALLS SHALL BE PROVIDED WITH U.L. APPROVED FIRE RATED ASSEMBLIES.

COORDINATION NOTES

CONTRACTOR TO COORDINATE ALL FINAL LOCATIONS, ANY TYPES OF ALL DEVICES, AND EQUIPMENT WITH ARCHITECT

LIGHTING NOTES

OF CABLE, AND FINAL LOCATIONS WITH OWNER/ARCHITECT PRIOR TO CONSTRUCTION. CONTRACTOR TO

DESIGN/BUILD AND COMPLY WITH NEC AND EIA/TIA STANDARDS

(EQUAL TO WALL FIRE RATING - SEE ARCHITECTURAL DRAWINGS)

2. CONTRACTOR SHALL COMPLY WITH FBC (C408.2.5.2). PROVIDE OWNER WITH OPERATIONAL MANUALS AND

ELECTRICAL SPECS, LEGEND & INDEX

ELECTRICAL SITE PLAN

ELECTRICAL RISER DIAGRAM

POWER PLAN

INSTALLATION DRAWINGS.

MAINTENANCE MANUALS.

PRIOR TO BID AND ROUGH-IN.

LIGHTING PLAN

DESCRIPTION

3. ARCHITECT TO SET MOUNTING HEIGHTS FOR ALL FIXTURES WHERE APPLICABLE, UNLESS OTHERWISE NOTED.

4. CONTRACTOR TO PROVIDE LUMINAIRES TO CONFORM TO ENERGY CODE, THERMAL ENVELOPE RATINGS.

EQUIPMENT/FEEDER REMOVAL NOTES

SALVAGED MATERIALS, EQUIPMENT, AND FEEDERS SHALL BE DELIVERED TO THE OWNER AT HIS PROPERTY AND STORED WITHIN THE BUILDING WHERE DIRECTED. ANY REMOVED MATERIALS OR EQUIPMENT WHICH THE OWNER DOES NOT WISH TO KEEP SHALL BE DISPOSED OF BY THE CONTRACTOR, WITHOUT ADDITIONAL COST TO THE OWNER.

SCOPE OF WORK

THE PROJECT CONSISTS OF A AMPHITHEATRE IMPROVEMENT WITHIN AN EXISTING SITE. UPGRADING ELECTRICAL SYSTEMS - POWER, LIGHTING, SIGNAL.

PROGRESS SET: 08/22/16


PRIOR TO SUBMITTING THE BID, THE CONTRACTOR SHALL FIELD VERIFY ALL EXISTING CONDITIONS AND INFORM THE ARCHITECT AND THE ENGINEER OF ANY DISCREPANCY BETWEEN THESE DOCUMENTS AND THE EXISTING CONDITIONS AND SHALL INCLUDE IN THE BID TO CORRECT THE SAME AS DIRECTED. THE ENGINEER AND THE ARCHITECT, ARE NOT RESPONSIBLE FOR ANY ADDITIONAL COSTS RESULTING URSULA IAFRATE, P.E. LICENSE #73122 FROM VERIFIABLE EXISTING CONDITIONS DISCOVERED AFTER CONTRACT HAS BEEN AWARDED. NO CHANGES SHALL BE MADE TO THESE PLANS WITHOUT PRIOR APPROVAL FROM THE ENGINEER OF RECORD. ALL CHANGES SHALL BE SUBMITTED FOR REVIEW PRIOR TO INSTALLATION. NOT FOR BID UNTIL PERMIT HAS BEEN ISSUED.


PROGRESS OR CHECK SETS, BY THEIR NATURE, MAY BE INCOMPLETE AND ARE NOT TO BE USED FOR BIDDING OR CONSTRUCTION. CONTRACTOR RECOGNIZES HIS SOLE RESPONSIBILITY TO INCLUDE ALL CONTINGENCIES FOR

DESIGN AND INSTALLATION TO MEET THE PROJECT REQUIREMENTS IN ANY PRICING EXERCISE.

700 WEST HILLSBORO BLVD. - BLDG. #1, SUITE 204 DEERFIELD BEACH, FLORIDA 33441 TEL: (561) 391-9292 FAX: (561) 391-9898 CERTIFICATE OF AUTHORIZATION NO. 28107

STEPHEN F. ROLLIN, P.E. LICENSE #36428 DONALD H. AUSTIN, JR., PE LICENSE #60651 JASON BARBER, P.E. LICENSE #73050 E-MAIL: INFO@FAECONSULTING.COM PM: BJ P/N 16028 DESIGNED BY: RB/SK/JS





RICK GONZALEZ. A.I.A PRESIDENT AR - 0014172 300 CLEMATIS STREET WEST PALM BEACH FLORIDA PH: (5 6 1) - 6 5 9 - 2 3 8 3 FAX: (5 6 1) - 6 5 9 - 5 5 4 6

www. regarchitects. con **CORPORATION NUMBER**

11600 POINCIANA BLVD. ROYAL PALM BEACH, FL 3341

REVISIONS DATE 06-30-16 **SCALE** AS NOTED RB/FR/JS DRAWN

(c) 2016 OWNERSHIP AND USE OF THESE DOCUMENTS & SPECIFICATIONS AS INSTRUMENTS OF SERVICE ARE AND SHALL REMAIN THE PROPERTY OF THE ARCHITECT WHETHER THE PROJECT THEY ARE MADE FOR IS EXECUTED OR NOT. THEY SHALL NOT BE USED BY THE OWNER OR OTHERS ON OTHER PROJECTS OR FOR ADDITIONS TO THIS PROJECT BY OTHERS, EXCEPT BY AGREEMENT IN WRITING AND WITH APPROPRIATE COMPENSATION TO THE ARCHITECT

DA/SR

CHECKED

REG No.