

○
○
○
○
○
○
○
○
○
○

BULLETIN LOG



**WESTLAKE AUXILIARY
 SALES CENTER**
 CITY OF WESTLAKE
 PALM BEACH COUNTY, FLORIDA

ISSUE DATE: -- 09-30-16
 ISSUED FOR: PERMIT
 BUILDING SHELL ONLY

△
△
△
△
△
△
△
△
△
△

REVISION LOG

EAG
 PROFESSIONAL ENGINEERING, INC. B
 14912 Melleo Ave Dr - Lutz, FL - 33558
 Ph: 813.963.1906 Fax: 813.489.4666
 Alan C. Guenther, P.E. #33308 / C.A. #28813

ALAN C. GUENTHER, PE #53308

TO THE BEST OF THE KNOWLEDGE OF THE ARCHITECT AND ENGINEER, THIS PLAN AND SPECIFICATIONS COMPLY WITH THE APPLICABLE MINIMUM BUILDING CODES AND THE APPLICABLE MINIMUM SAFETY STANDARDS.

**WESTLAKE AUXILIARY
 SALES CENTER**
 PROJECT NAME

FOUNDATION PLAN

SHEET NAME

PROJECT NUMBER: 2016.082

DRAWN BY: MAK CHECKED BY: ACG

SCALE: SEE SHEET

S1.1
 SHEET NUMBER

- FOUNDATION PLAN NOTES:**
- NEW AND FUTURE INTERIOR SLAB-ON-GRADE TO BE 4" THICK (3,000 PSI) w/ #6 @ 16" O.C. W/W/4 W/W/4 ON 10 MIL VAPOR BARRIER OVER COMPACTED AND TERMITE TREATED SOIL U.N.O. REFER TO 1/S3.1 FOR SLAB CONTROL JOINT.
 - TOP OF SLAB ELEVATION = 0'-0" U.N.O.
 TOP OF EXTERIOR FOOTING ELEVATION = (-) 1'-4" U.N.O.
 < > INDICATES TOP OF FOOTING ELEVATION.
 - CENTER ALL FOOTINGS BELOW WALL OR COLUMN U.N.O.
 - ALL FOOTING REINFORCING TO BE BOTTOM BARS U.N.O.
 - PROVIDE 10" MIN. SOIL COVER OVER ALL EXTERIOR FOOTINGS. NOTIFY ENGINEER OF ANY CONFLICTS OR DISCREPANCIES.
 - REFER TO ARCHITECTURAL/CIVIL FOR EXTERIOR SLAB AND SIDEWALK INFORMATION.
 - REFER TO ARCHITECTURAL/PLUMBING DRAWINGS FOR FIXTURE/DRAIN LOCATIONS AND REQUIREMENTS.
 - SEE PLAN FOR MASONRY CONTROL JOINT (M.C.J.) LOCATIONS. COORDINATE WITH ARCHITECTURAL ELEVATIONS. REFER TO 3/S3.1 FOR MASONRY CONTROL JOINT DETAIL.
 - ALL WALL FOOTINGS TO BE TYPE "WF2" U.N.O.
 - PROVIDE CORNER BARS AT ALL CORNERS AND INTERSECTIONS OF CONTINUOUS FOOTINGS. REFER TO DETAIL 2/S3.1 FOR MORE INFO.
 - REFER TO 1/S2.1 FOR DESIGN WIND CRITERIA.

FOOTING SCHEDULE

MARK	SIZE	DEPTH	REINFORCING	COMMENTS
WF2	2'-0" WIDE X CONT.	1'-0"	(3) #5 CONT. W/ #5 TRANSV. AT 48" O.C. BOTTOM	WALL FOOTING
F5	5'-0" X 5'-0"	1'-0"	(5) #5 EACH WAY, BOTTOM	COLUMN FOOTING
F8	8'-0" X 8'-0"	1'-8"	(8) #6 EACH WAY, TOP AND BOTTOM	COLUMN FOOTING

