



EQUIPMENT SCHEDULE		
ITEM NO	QTY	EQUIPMENT CATEGORY
1848	1	SHELVING, WIRE
B1	1	UNDER BAR ICE CHEST
B2	1	UNDER BAR HAND SINK
B2.1	1	UNDER BAR SPEED RAIL
B3	4	UNDER BAR DRY WASTE
B4	1	BACK BAR EQUIPMENT
B5	2	UNDER BAR DRY STORAGE
B5.5	1	COOLER, BOTTLE
B6	1	GLASS WASHER
B7	1	UNDER BAR FILLERS & DRAIN BOARDS
B8	1	UNDER BAR ALL-IN-ONE STATION
B9	1	COOLER, BOTTLE
B10.1	1	DISPENSING HEAD, DRAFT BEER, BREW PIPE PT TOWER
B10.2	1	DROP-IN, DRAINERS
K1	1	TABLE, WORK, 16 GAUGE, BACK SPLASH W/ UNDER SHELF
K1.1	1	FAUCET, DECK MOUNT
K2	1	REFRIGERATOR, SANDWICH/SALAD PREP
K3	1	FREEZER, WORK TOP
K3.1	1	SHELF, WALL MOUNT
K4	1	WARMER, FOOD, ELECTRIC
K5	1	OVEN, PIZZA
K5.1	1	SHELF, WALL MOUNT
K6	1	RANGE, RESTAURANT, GAS
K6.1	1	CHEESEMELTER, GAS
K7	1	REFRIGERATOR, SHORTY
K7.1	1	GRIDDLE, GAS
K8	2	FRYER, DEEP FAT, GAS
K9	1	TABLE, WORK, 16 GAUGE, BACK SPLASH W/O UNDER SHELF
K9.1	2	SHELF, WALL MOUNT
K10	1	TABLE, WORK, 14 GAUGE, BACK SPLASH W/ UNDER SHELF
K10.1	1	SINK, WELDED INTO TABLE
K10.2	1	FAUCET, DECK MOUNT
K10.3	2	SHELF, WALL MOUNT
K11	1	DISH TABLE, STRAIGHT, 16 GAUGE
K11.1	1	PRE-RINSE FAUCET, BACKSPLASH MOUNT
K12	1	WARE WASHER, DOOR TYPE, HIGH TEMP
K13	1	DISH TABLE, STRAIGHT, 16 GAUGE
K14	1	SINK, NSF, 3 COMP, 16 GAUGE
K14.1	1	FAUCET, BACKSPLASH MOUNT
K14.2	2	SHELF, WALL MOUNT
K15	1	HAND SINK, WALL MOUNT
K16	1	SINK, MOP
K16.1	1	SERVICE SINK FAUCET
K17	1	ICE MAKER W/O BIN
K17.1	1	BIN, ICE
K17.2	1	FILTER SYSTEM, ICE MAKER
K18	3	FLOOR TROUGH

- GENERAL CONTRACTOR RESPONSIBILITIES INCLUDE**
1. VERIFY THAT ALL DIMENSIONS SHOWN COMPLY WITH BUILDING CONDITION.
  2. ALL ELECTRICAL AND PLUMBING CONNECTIONS. THIS INCLUDES GAS LINES, RESTRAINING DEVICES, WATER LINES, DRAIN LINES, WIRING, ETC.
  3. GENERAL CONTRACTOR SHALL INSTALL BACKING FOR THE FOLLOWING ITEMS:  
 WALL SHELVES FROM 57" TO 75" AFF.  
 HAND SINKS FROM 30" TO 54" AFF.  
 POT SINKS FROM 30" TO 42" AFF.  
 PREP TABLES W/SINK FROM 30" TO 42" AFF.  
 MOP SINKS FROM 48" TO 78" AFF.  
 FIRE SUPPRESSION SYSTEM FROM 12" TO 108" AFF.  
 HOSE REELS FROM 12" TO 108" AFF. (SEE DETAIL SPEC. SHEET)  
 WATER FILTERS FROM 54" TO 72" AFF.
  4. SUPPLY WATER HEATER. (TO BE INSTALLED BY PLUMBER)
  5. RESPONSIBLE FOR FINAL HOOK-UPS ON ALL PIECES OF EQUIPMENTS.
  6. UNLOAD EQUIPMENT FROM DELIVERY TRUCKS.
  7. ASSEMBLY OF EQUIPMENTS.
  8. PLACEMENT OF EQUIPMENT PER PLAN.
  9. SECURING SINKS TO WALLS. (REQUIRES WALL BACKING)
  10. HANG WALL SHELVES. (REQUIRES WALL BACKING)
  11. START-UP OF THE EQUIPMENT IS INCLUDED.



RODOLFO ACEVEDO AIA  
 JAMES R. WILLIAMS AIA  
 7700 CONGRESS AVE.  
 SUITE 1114  
 BOCA RATON, FLORIDA 33487  
 TEL 561 997 1244  
 FAX 561 997 1675  
 JAMES R. WILLIAMS - AR0017581  
 RODOLFO ACEVEDO - AR0016334

211 E OCEAN AVENUE  
 BOYNTON BEACH, FL 33435

FLORIDA LICENSEURE:  
 AA26002219

PROJECT NO: 15196  
 DESIGNED BY: Designer  
 DRAWN BY: Author  
 CHECKED BY: Checker

SUBMITTALS:  
 PERMIT SET 11.23.2016

REVISIONS:

EQUIPMENT PLAN

A43

1 EQUIPMENT PLAN  
 SCALE: 3/8" = 1'-0"

©2016 AW ARCHITECTS, INCORPORATED ALL RIGHTS RESERVED. NO PART OF THESE IDEAS, PLANS OR DESIGNS MAY BE REPRODUCED, COPIED OR UTILIZED GRAPHICALLY IN ANY FORM WHATSOEVER WITHOUT THE EXPRESSED WRITTEN CONSENT OF AW ARCHITECTS INCORPORATED AND ITS BOARD OF DIRECTORS.