



LIGHTING PLAN
3/32"=1'-0"

KEY NOTES	
1	INSTALL SCUNCES AT EXISTING OUTLET LOCATIONS, CIRCUIT THROUGH MAIN LIGHTING CONTROL.
2	TIE TO EXISTING HALLWAY LIGHTING CIRCUIT AND CONTROL POINT.
3	TIE TO EXISTING ROOM LIGHTING CIRCUIT AND CONTROL POINT.
4	REMOVE EXISTING CHANDELIER THIS AREA. COORDINATE DISPOSAL WITH OWNER.
5	EXISTING HI-HATS TO BE REPLACED ONE-FOR-ONE WITH NEW LED FIXTURES.
6	LIGHTING CONTROL PANEL FOR SPECIALTY LIGHTING, COORDINATE WITH MANUF.
7	RELOCATE LINEAR DIFFUSER AS REQUIRED. TRIM/EXTEND FLEX AS REQUIRED.

ISSUED FOR PERMIT ONLY		04-18-16
KAMM CONSULTING PROJECT # 2016-0292		
PROJECT MANAGER: JOHN MAYR		
1408 Orange Avenue Fort Pierce, Florida 34950 Phone 772.595.1744 Fax 772.595.1745 bbrown@kammconsulting.com Certification of Authorization #8189		
PRINCIPAL Brady L. Brown	Florida License #58232	04-18-16 date signed

LIGHTING PLAN