


CA. LIC. No. 31328



CHECK SET: 05/20/16

SHEET # 1600 SOUTH DIXIE HWY., SUITE 400 BOCA RATON, FLORIDA 33432 PHONE 561-391-0081 FAX 561-391-0085 Linares EMAIL mail@rwb-arch.com ARCHITECTURE

LIFE FELLOWSHIP 11401 WEST SAMPLE ROAD

MAINTAIN MINIMUM 10'-O" BETWEEN ALL FRESH AIR INTAKES [AH-2, 3, 4, 5, &6, ERV-1] AND ALL PLUMBING AND EXHAUST VENIT TERMINATIONS.

SEE ARCHITECTURAL PLANS FOR ROOF ACCESS.

2 NOT USED.

3 PROVIDE GELV WP / WR ROOFTOP RECEPTACLE WITHIN 25' OF ALL MECHANICAL EQUIPMENT. SEE ROOFTOP EQUIPMENT MOUNTING DETAIL ON SHEET ES!.

CONTRACTOR TO MAINTAIN A 30" WIDE AND 3"-O" DEEP CLEAR AROUND ALL ELECTRICAL DISCONNECTING MEANS FOR ALL EQUIPMENT. CONTRACTOR SHALL ENSURE THERE A MAINTENANCE RECEPTAGLE WITHIN 25" OF THE EQUIPMENT.

EQUIPMENT DISCONNECTS:

REVISIONS