



REGISTRATION SEAL



() CEILING START POINT.

2 EXISTING COLUMN.

Z) EXISTING COLUM

(3) EXISTING EXTERIOR LIGHTING TO REMAIN.

NEW AWNINGS BY TENANT VENDOR. G.C. TO COORDINATE INSTALLATION.

CEILING PLAN NOTES

- CONTRACTOR TO NOTIFY DESIGNER OF ANY DISCREPANCIES OR CONFLICT IN INTENT IN ACCOMPLISHING CEILING WORK PRIOR TO AWARD OF CONTRACT OR IT WILL BE ASSUMED ALL NECESSARY WORK AND COSTS ARE INCLUDED.
- CONTRACTOR TO REVIEW DUCTWORK RUNS AND HEIGHTS AND TO COORDINATE AND ACCOMPLISH DESIRED DESIGN CRITERIA.
- 3. THE CONTRACTOR PRIOR TO BID, SHALL CHECK AND VERIFY ALL CEILING HEIGHTS, SLAB HEIGHTS FOR CLEARANCES AND INSTALLATION METHODS. HEIGHTS AND LOCATIONS OF ALL DUCTWORK, DIFFUSER UNITS, CONDUIT, JUNCTION BOXES, AND OTHER CEILING INSTALLATION TO BE COORDINATED PRIOR TO INSTALLATION.
- 4. CONTRACTOR SHALL CHECK AND VERIFY ALL CEILING PLENUM CONDITIONS FOR CLEARANCES OF DUCTWORK, LIGHT FIXTURES, SPRINKLERS, ETC., BEFORE PROCEEDING WITH WORK AND SHALL NOTIFY DESIGNER OF ANY DISCREPANCIES.
- 5. ALL PIPES AND DUCTS SHALL BE ABOVE HUNG CEILING, NOTIFY DESIGNER OF ANY DISCREPANCIES.
- 6. CEILINGS TO BE INSTALLED ACCORDING MANUFACTURES PUBLISHED INSTALLATION REQUIREMENTS & LOCAL CODE REQUIREMENTS.
- ALL DIMENSIONS OF LIGHTING FIXTURES ARE GIVEN CENTER TO
- CENTER UNLESS OTHERWISE NOTED. ALL LIGHT FIXTURES TO ALIGN UNLESS OTHERWISE NOTED.

 8. G.C. TO ENSURE ALL SALES AREA LIGHTING AT OR AROUND WALL
- FIXTURES WILL BE ACCESSIBLE FOR MAINTENANCE. LIGHTING SHOULD BE ACCESSIBLE FROM SALES AREA SIDE, NOT WALL SIDE, AROUND WALL FIXTURES WITH UPPERS. TYP.

 9. ALL SWITCH PLATES AND OUTLET PLATES TO BE WHITE.

 10. ALL LIGHT SWITCHES SHALL BE INSTALLED 38" AFF WITH CENTER
- LINE OF FIRST SMITCH 6" FROM ADJACENT DOOR BUCK OR ADJACENT WALL INTERSECTION UNLESS OTHERWISE NOTED. WHERE MORE THAN ONE SMITCH OCCURS IN THE SAME LOCATION, THEY SHALL BE INSTALLED IN GANG TYPE BOX UNDER ONE COVER PLATE.
- REFER TO ENGINEERING DRAWINGS FOR ALL A.C. SUPPLY, RETURN AIR DIFFUSERS AND EXHAUST FANS.
- 12. ALL FLUORESCENT LIGHT FIXTURES TO HAVE ELECTRONIC BALLAST/COOL WHITE BULBS.
- 13. REFER TO ELECTRIC PANEL SCHEDULE FOR LIGHTING FIXTURE VOLTAGE REQUIREMENTS.
- 14. CEILING SPEAKER PROVIDED AND INSTALLED BY SOUND SYSTEM VENDOR SEE SHEET T2.0 FOR VENDOR INFORMATION.
- 15. G.C. TO VERIFY HEIGHTS OF WINDOW MULLIONS TO COORDINATE WITH SOFFIT DETAILS. NOTIFY VITAMIN SHOPPE PM WITH ANY

·

REVISIONS: ⚠ 06/30/16 OWNER COMMENTS	
REVIS	
	150710
PROJECT NO. DATE:	150310 10/14/15
DRAWN BY:	RAR
STORE NUMBER:	404

PROTO: 2016R1 PROTOTYPE SET


SALES AREA 2,420 S.F.

NON SALES 588 S.F.

GROSS AREA 3,008 S.F.

HEET TITLE:

REFLECTED CEILING PLAN + NOTES





SHEET NO:

A3.0