

## GENERAL NOTES

- 1. CONTRACTOR SHALL REMOVE ALL DUCTWORK AND UNITS THAT ARE BEING UNUSED.
- 2. CONTRACTOR SHALL CAP OR SEAL ANY UNUSED OPENINGS OR EXISTING PENETRATIONS AT UNITS THAT WERE REMOVED.

## KEY NOTES

- 1 PROVIDE SERVICE ACCESS PER MANUFACTURER REQUIREMENTS AND NEC.
- 2 4" DRYER EXHAUST DUCT TO X-VENT WALL LOUVER..
- 3 30X14 SUPPLY AIR DUCT UP TO 0ARTU-2 ON ROOF
- (4) 30X14 SUPPLY AIR DUCT UP TO OARTU-1 ON ROOF
- 5 INTERLOCK EXHAUST FAN WITH OARTU-2
- 6 INTERLOCK EXHAUST FAN WITH OARTU-1
- 7 CONTRACTOR SHALL ROUTE EXISTING REFRIGERANT LINES BACK TO EXISTING CONDENSING UNIT.
- 8 RELOCATE EXISTING SMOKE DETECTOR AS SHOWN; PROVIDE NEW IF EXISTING NOT FUNCTIONAL.

IDDCED FOR FERMIT	
ISSUED FOR CONSTR	UC

KAMM CONSULTING PROJECT #: 2016-0501 PROJECT MANAGER: NICK RODRIGUEZ

**Consulting** 1407 West Newport Center Drive Deerfield Beach, Florida 33442 Phone 954.949.2200 Fax 954.949.2201 engineering@kammconsulting.com Certification of Authorization #8189 08-04-2016

08-04-2016

date

signed

SIEVEN E. MYOIT	boynton beach, florida www.semarchitecture.com p: 561.734.7034	
Cany Can'n - INTERIOR RENOVATION -	PENN DUTCH PLAZA 3191 SR7 MARGATE, FLORIDA 33063	
ARCHITECT	TECT'S	
ALL DRAWINGS AND WRITTEN MATERIAL APPEARING HEREIN CONSTITUTE ORIGINAL AND UNPUBLISHED WORK OF THE ARCHITECT AND MAY NOT BE USED, DUPLICATED OR DISCLOSED IN ANY FORM WITHOUT THE EXPRESSED WRITTEN CONSENT OF THE ARCHITECT		
PROJECT NO: DRAWN BY: CHECKED BY: <u>NO: DATE: ISS</u>	16.049 57 59 UED FOR:	
<u>  05202016 PRE</u>	MIT / BIDDING	
MECHA PL		
M	2.1	

PRINTED ON: 8-4-2016