



**SEQUENCE TWO  
 PROPOSED FLOOR PLAN**  
 SCALE: 3/16" = 1'-0"

**KITCHEN FINISH NOTES:**

- GC SHALL PROVIDE NEW POURED RESIN FLOOR PER SPECIFICATIONS. REFER TO SHEET ID-1 FOR FLOOR PATTERN. FLOOR SHALL HAVE TWO SHADES, PER SHEET ID-1.
- WHERE NEW FLOORING ABUTS EXISTING VCT FLOORING PROVIDE TRANSITION STRIPS PER DETAIL. REFER TO SHEET A-5.
- GC SHALL PROVIDE NEW DIAMOND TREAD FLOOR IN FREEZER AND COOLER. ALUMINUM DIAMOND PLATE TO BE 6061-T6 MILL FINISH, 1/4" THICK, BY EVANSVILLE SHEET METAL WORKS, INC. OR APPROVED EQUAL.
- FOR MORE INFORMATION ABOUT FINISHES, SEE INTERIOR ELEVATIONS ON SHEET A-4, DETAILS ON SHEET A-5, AND FLOOR FINISH PLAN ON ID-1.

**RECEIVING AREA FINISH NOTES:**

- ELEMENTS TO BE PAINTED SHALL BE PAINTED BENJAMIN MOORE, COLOR AS PER FINISH LEGEND ON SHEET A-4.
- GC SHALL PROVIDE NEW RETURN AIR GRILLES WHERE NEEDED.

**GENERAL NOTES:**

- THE WORK SHALL BE SUBSTANTIALLY COMPLETED WITHIN 180 CALENDAR DAYS FROM THE PROJECT INITIATION DATE SPECIFIED IN THE SECOND NOTICE TO PROCEED, AND COMPLETED AND READY FOR FINAL PAYMENT IN ACCORDANCE WITH ARTICLE 6 OF THE CONTRACT WITHIN 30 CALENDAR DAYS FROM THE DATE OF SUBSTANTIAL COMPLETION. THE 180 CALENDAR DAYS INCLUDE 7 CALENDAR DAYS TO RELOCATE EXISTING KITCHEN EQUIPMENT TO TEMPORARY SERVING BY KITCHEN OPERATOR UPON COMPLETION OF SEQUENCE ONE AND 7 CALENDAR DAYS TO RELOCATE EXISTING KITCHEN EQUIPMENT TO RENOVATED KITCHEN BY KITCHEN OPERATOR UPON COMPLETION OF SEQUENCE TWO.
- REFER TO CINI-LITTLE INTERNATIONAL, INC.'S SHEETS QF-101 THROUGH QF-106 AND QF-201 THROUGH QF-207 FOR KITCHEN EQUIPMENT AND NOTES.

**LEGEND**

- EXISTING WALL/PARTITION TO REMAIN
- EXISTING CMU WALL TO REMAIN
- NEW WALL/PARTITION
- TEMPORARY DRYWALL PARTITION
- NEW ALUMINUM DIAMOND TREAD FLOORING
- FIRE EXTINGUISHER (AT NEW TYPE K, PLACE A PLACARD PER NFPA 10 INDICATING THAT HOOD EXTINGUISHING SYSTEM SHALL BE ACTIVATED BEFORE USING THE EXTINGUISHER.)